



October 1, 2012

ADDENDUM NO. 1
TO THE CONTRACT DOCUMENTS
For the Construction of
Dorland Ave at Cabarrus Ave Roadway Realignment
City of Concord
850 Warren C. Coleman Boulevard
Concord, NC 28206

TO ALL PLANHOLDERS:

The bid date and time has **NOT** changed by this addendum. Bids will be received in Conference Room C Alfred M. Brown Operations Center, 850 Warren C. Coleman Blvd. (Hwy 601 S.), Concord, NC 28026 until 2:00 PM on October 2, 2012.

The following clarifications, changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of Dorland Ave at Cabarrus Ave Roadway Realignment as fully and completely as if the same were fully set forth therein:

SECTION I – BIDS, AGREEMENTS AND NOTICES

A. **BID FORM:** REPLACE the BID FORM with the attached revised version. Bid item 10 was revised to remove the labeling of 6%. Project Special Conditions #6 cover the approximate asphalt binder content of the asphalt.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 in the designated boxes as provided in the BID FORM.

Sincerely,

A handwritten signature in black ink that reads "M. Sue Hyde".

M. Sue Hyde, PE
Engineering Director

EXHIBIT A – BID FORM
DORLAND AVE AT CABARRUS AVE ROADWAY RE-ALIGNMENT
Project No. 2008-035

			QTY	UNIT	COST/UNIT	SUBTOTAL
1	800	Mobilization	LS	1		
2	225	Undercut Excavation	CY	260		
3	226	Grading	LS	1		
4	520	Aggregate Base Course	TON	538		
5	545	Incidental Stone Base	TON	75		
6	270	Geotextile for soil stabilization	SY	200		
7	607	Milling Asphalt Pavement, varies - 3" max	SY	330		
8	610	Asphalt Concrete Intermediate Course 2.25" Type I19.0B	TON	114		
9	610	Asphalt Concrete Surface Course 2" Type SF9.5A	TON	100		
10	610	Asphalt Binder for Plant Mix	TON	15		
11	801	Construction Surveying	LS	1		
12	SP-2	Sawcut ex. Asphalt for curb & gutter on Cabarrus	LF	108		
13	846	2'6" Concrete Curb & Gutter	LF	650		
14	848	4" Concrete Sidewalk	SY	264		
15	848	6" Concrete Driveway NCDOT 848.03 to back of R/W	SY	30		
16	848	Concrete Curb Ramps per NCDOT Detail	EA	4		
17	1205	Thermoplastic Pavement Marking Symbols, 90 mil	EA	6		
18	1205	Thermoplastic Pavement Marking Lines, 4", 120 mil	LF	60		
19	1205	Thermoplastic Pavement Marking Lines, 24", 120 mil	LF	540		
20	1205	Removal of Pavement Marking Lines, 24"	LF	15		
21	Sheet 14	Temporary Silt Fence	LF	500		
22	SP-3	Inlet Protection	EA	2		
23	Sheet 14	Stone Outlet At Sediment Fence	EA	1		
24	1660	Seeding and Mulching	AC	.5		
25	Concord	Fire Hydrant Assembly	EA	1		
26	WSACC	6" Gate Valve for fire hydrant	EA	1		
27	WSACC	6" DIP for fire hydrant leg	LF	10		
28	WSACC	8" PVC water main	LF	115		
29	WSACC	8" gate valve	EA	1		
30	WSACC	8" x 45-deg PVC bends	EA	3		
31	Concord	Install new 3/4" short side water service & meter, if necessary	EA	2		

32	Concord	Install new sanitary sewer services/COs, if necessary	EA	2		
33	Cabarrus Co	Plumbing for new water & sewer services, if necessary	EA	2		
34	WSACC	Plug & abandon in place ex. 8" ex water line	LS	1		
35	WSACC	Cut in 8" valve on ex. 8" water line	EA	1		
36	SP-1	Traffic Control	LS	1		

ESTIMATED BASE COST

\$ _____

10% CONTINGENCY

\$ _____

TOTAL ESTIMATED COST

\$ _____

5. Bidder agrees that all work will be completed and ready for final payment in accordance with Paragraph 14.13 of the General Conditions within 90 days from the date of notice to proceed.