

## **ADDENDUM 1**

**TIP Number: C-4918A**

**County: Cabarrus**

**Poplar Tent (SR1394) and US 29 Intersection Improvements**

**October 31, 2017**

1. Detail added for pavement repair. Attached.
2. Revised detail for 4" water meter vault. Attached.
3. Revised Unit Price Schedule modifying some drainage items to match the plan sheets, adding a pay item for asphalt pavement repair, adding a pay item for concrete driveway. Attached.
4. Clarification on driveway tie-ins – typical section.
  - Approx. Station 24+50 RT (-L-) – 10" ABC or 5" Asphalt Concrete Base Course, Type B25.0B and 2" Asphalt Concrete Surface Course, Type S9.5B
  - Approx. Station 24+00 to 26+00 LT (-Y1-) – Both driveways to be concrete and match existing concrete depth.
  - Approx. Station 12+25 RT (-L-) – Use same typical as bulb
  - Approx. Station 15+00 RT (-L-) – 1.5" Asphalt Concrete Surface Course, Type S9.5B
  - Approx. Station 16+25 RT (-L-) - 1.5" Asphalt Concrete Surface Course, Type S9.5B
5. This addendum shall become a part of the drawings and specifications for the above project.

End of Addendum 1