

EXHIBIT A – BID FORM

**30 Market St. Sewer Relocation- Bore Option
Project No. 2018-058**

No.	Item NCDOT	Description	Units	QTY.	Unit Price	Item Total
1	800	Mobilization	LS	1		
2	SP-05	Comprehensive Grading	LS	1		
3	801	Construction Surveying	LS	1		
4	SP-01	Traffic Control, provide and maintain all signs	LS	1		
5	WSACC 02620	10-inch Restrained DIP Sanitary Sewer Main (14-16 feet)	LF	33		
6	WSACC 02628	12-inch PVC Sanitary Sewer Main (14 - 16 feet)	LF	16		
7	WSACC 02628	12-inch PVC Sanitary Sewer Main (8 - 10 feet)	LF	42		
8	WSACC 02605	5' Dia. Sanitary Sewer Manhole (MH-1) Including Inside Drop	EA	1		
9	WSACC 02605	5' Dia. Sanitary Sewer Manhole Extra Depth	LF	9		
10	WSACC 02605	Tie in into Ex MH A (including inside drop)	EA	1		
11	WSACC	Trenchless Crossing <u>in Soil</u> (All Inclusive - 24" Casing Pipe, 10" restrained DIP Carrier Pipe)	LF	45		
12	WSACC	Trenchless Crossing <u>not in Soil</u> (All Inclusive 24" Casing Pipe, 10" restrained DIP Carrier Pipe)	LF	35		
13	WSACC 02605	Tie in into Ex MH C and MH F	EA	2		
14	WSACC	Pump Around	LS	1		
15	SP-02	Storm Drain Inlet protection	EA	1		
16	848	Concrete pavement replacement at City Hall Alley	SY	45		
17	848	Concrete Pavement replacement, Carolina Court	SY	225		
18	846	2'-6" Concrete Curb and gutter replacement, Carolina Court.	LF	40		
19	610	Surface Course 1.5" S9.5B	TON	5		
20	610	Intermediate Course 5.0" I19.0C	TON	7		
21	620	Asphalt Binder for Plant Mix	TON	4		
22	520	8" ABC Base Course	TON	20		
23	607	Milling Asphalt Pavement, 0" to 1 1/2" Depth	SY	10		
24	270	NCDOT 1056 – Geotextile for soil stabilization, Type 4 (Mirafi 500 X or equivalent)	SY	100		
25	SP-03	Select Material	Tons	50		

26	SP-04	Remove and replace Carolina Court sign.	LS	1		
27	NCDOT 1530	Abandon Existing MH B (Fill with Select Material).	LS	1		
28	NCDOT 1530	Abandon existing 10-inch PVC line between MH C And B, and Between MH C and A. (Plug both ends of the pipe with grout)	EA	2		

ESTIMATED BASE COST \$ _____
10% CONTINGENCY \$ _____
TOTAL ESTIMATED COST \$ _____

5. Bidder agrees that all work will be completed and ready for final payment in accordance with Paragraph 14.13 of the General Conditions within 90 days from the date of notice to proceed.

6. Liquidated damages are \$250.00 per each day past the contract completion date.

7. Communications concerning this Bid shall be sent to Bid at the following address:

NAME: _____

ADDRESS: _____

P.O. BOX: _____

CITY: _____

STATE: _____

ZIP: _____

8. The terms used in this BID, which are defined in the General Conditions of the WSACC Specifications, have the meanings assigned to them in the General Conditions.

SIGNATURE OF BIDDER: _____

Contractor's License Number _____

License Expiration Date _____

If an Individual

By _____
 (signature of individual)

doing business as _____

Business address _____

Phone No. _____

SP-05, COMPREHENSIVE GRADING

1.0 DESCRIPTION

This item shall include all elements of work covered by the referenced NCDOT Specifications and the numbered Additional City Specifications provided herein.

NCDOT Specifications

200, "Clearing and Grubbing"
225, "Roadway Excavation"
235, "Embankments"
240, "Ditch Excavation"
250, "Removal of Existing Pavement"
260, "Proof Rolling"
340, "Pipe Removal"
412, "Unclassified Structure Excavation"
416, "Channel Excavation"
500, "Fine Grading, Sub-grade, Shoulders and Ditches"
545, "Incidental Stone Base"
560, "Shoulder Construction"
1530, "Abandon or Remove Utilities"
1607, "Gravel Construction Entrance"

Additional City Specifications

1. Traffic Bearing Road Plates: The Contractor shall be responsible for all traffic bearing road plates needed in accordance with NCDOT Utility Cut Replacement Detail.
2. Fence Removal and Disposal and or Fence Relocation: as shown on the plans and any additional removal or relocation identified by the Contractor's means and methods shall be included in this item.
3. Removal and Disposal of Existing Infrastructure: concrete curb, sidewalk, miscellaneous concrete, asphalt, driveways, pads, slabs, walls, culverts, structures, catch basins, manholes, etc. within the construction limits as shown on the plans and any additional infrastructure removal identified by the Contractor's means and methods shall be included in this item.
4. Shoring: The Contractor shall be responsible for all shoring to include means, methods, materials and engineering needed to construct the project.
5. Saw Cutting: all saw cutting required to build the Project. Where asphalt or concrete (curb, sidewalk, roadway, driveways, parking lots, etc.) is to be removed, the Contractor shall provide a neat edge along the pavement being retained by sawing the pavement a minimum of 2" deep and 1' wide before breaking and removing adjacent pavement. When the Contractor proposes to saw pavement more than one foot from the proposed pavement (curb, sidewalk, structure, etc.), the

Contractor shall obtain approval from the Engineer prior to saw cutting and removing pavement. The cost of sawing asphalt or concrete shall be included in this item.

6. Sidewalk and Curb Clean-up: The Contractor shall have all related sidewalk and curb work completed within ten (10) days of placement, including but not limited to 1) removal and disposal of construction debris; 2) related grading to include fine grading; 3) site restoration; 4) seedbed preparation and dress up work; 5) seeding and mulching; and 6) final cleaning.

7. Water Meter / Sewer Clean Out Protection: all labor and materials required to protect, and replace if necessary, impacted water meters and sewer clean outs in the work area.

8. Utility Pipe/Conduit Removal and Disposal: existing public or private utility pipe / conduit, subsurface and shoulder drain pipe removal and disposal as shown on the plans and any additional utility pipe / conduit removal identified by the Contractor's means and methods shall be included in this item.

2.0 MEASUREMENT

There will be no separate measurement made for Comprehensive Grading.

3.0 PAYMENT

For the above-referenced NCDOT sections and numbered Additional City Specifications, there will be no direct measurement, payment or compensation, all cost incurred to complete the work as specified shall be included in the Lump Sum price bid for "Comprehensive Grading".

There will be **no separate measurement or payment** for the items listed or referenced in this specification.

Payment will be made under:

COMPREHENSIVE GRADINGLS